



# City of Palm Springs

Department of Building & Code Enforcement  
3200 East Tahquitz Canyon Way, Palm Springs CA 92262  
PO Box 2743, Palm Springs CA 92263  
Tel 760.323-8242 P Fax 760.322.8360 P TDD 760.864.9527  
[www.palmsprings-ca.gov](http://www.palmsprings-ca.gov)

## Wood / Stucco Garden Wall 2013

Design is limited to six (6) foot maximum high non-retaining walls.

### Notes:

1. This is not a retaining wall
2. Height of wall is measured from top of footing to top of wall.
3. All lumber in contact with concrete must be treated.
4. 1/2" x 10" anchor bolts placed 12" from posts and 6'0" oc. maximum.
5. Place plaster ground a min of 4" above grade.
6. **Disclaimer:** Alternate designs may be possible when provided with engineered analysis. Use of this standard design is at the user's risk and carries no implied or inferred guarantee

### Inspections:

1. Footing: After trenching, but prior to pour.
2. Framing: Prior to covering any work.
3. Final: When all work is complete.

